BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/09/2012-13 Dated: 13-12-2013

APPROVED TENDER SCHEDULE –'B'

Item No: 25

Name of Work:- Construction of Culverts in ward No-02 of yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri DANANJAYA B R	
				Rate	Rate in Words
1	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	Cum	100.50	147.95	Rupees one hundred forty seven only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing lipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 141 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance	Sqm	100.50	76.28	Rupees seventy six and paise twenty eight only
3	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.692cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HCM of machinery, curing complete as per specifications. Specification No. KBS	Cum	15.81	4183.57	Rupeesfour thousand one hundred eighty three and paise fifty seven only

For Bruhat Bangalore Mahanagara Palike

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri DANANJAYA B R	
				Rate	Rate in Words
4	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reinforced machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification	Cum	66.21	5498.77	Rupees five thousand four hundred ninety eight and paise seventy seven only
5	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification	Qunt	57.00	7196.20	Rupees seven thousand one hundred ninety six and paise twenty only
6	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,buttresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. Specification	Sqm	250.60	264.30	Rupees two hundred sixty four and paise thirty only
7	RCC Precast covering slab for drain (10cm thick)	Sqm	27.00	1213.86	Rupees one thousand two hundred thirteen and paise eighty eight only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
UBMP, Bengaluru-64.